ARTIFICIAL TURF INSTALLATION COST

*Based on 1500 sq ft Install. Prices noted below are industry averages across all 50 states.

WITH GENESIS ECO DRAIN®		WITHOUT GENESIS ECO DRAIN®
Remove 6" Dirt	\$0	\$1,200
Soil Testing and Disposal for Dirt	\$0	\$1,800
4" 57 Stone	\$0	\$800
1" Stone Fines	\$0	\$450
2 Days Pay for Installation Crew	\$0	\$2,800
Equipment Rental for Stone Base Work	\$0	\$850
Ground Preparation	\$800	\$800
Composite Nailer Board	\$200	\$200
Genesis Eco Drain	\$3,000	\$0
Average 75oz US Artificial Turf	\$3,750	\$3,750
Average Infill Cost	\$1,200	\$1,200
1 Day Pay for Installation Crew	\$1,500	\$1,500
INSTALLATION TIME	1-1.5 Days	3-4 Days
TOTAL COST	\$10,450	\$15,350

PAVER INSTALLATION COST

*Based on 1500 sq ft Install. Prices noted below are industry averages across all 50 states.

	WITH GENESIS ECO DRAIN®	WITHOUT GENESIS ECO DRAIN®
Remove 6" Dirt	\$0	\$1,500
Soil Testing and Disposal for Dirt	\$0	\$2,200
4" 57 Stone	\$0	\$1,600
1" Stone Fines	\$0	\$450
2 Days Pay for Installation Crew	\$0	\$2,800
Equipment Rental for Stone Base Work	\$0	\$850
Ground Preparation	\$800	\$800
Paver Product	\$6,000	\$6,000
Leveling Sand	\$2,200	\$2,200
Genesis Eco Drain	\$3,000	\$0
1 Day Pay for Installation Crew	\$1,500	\$1,500
INSTALLATION TIME	1-1.5 Days	3-4 Days
		\$10,000
TOTAL COST	\$13,500	\$19,900

cost savings **\$4,900**

cost savings **\$6,400**