



Genesis Eco Drain[®]

**RECYCLABLE DRAINAGE SYSTEM
FOR USE UNDER ARTIFICIAL
GRASS AND PAVERS**

What is Genesis Eco Drain[®]?



The Genesis Eco Drain[®] System was designed to revolutionize the way artificial grass and pavers are installed and increase artificial turf lifespan. The first product of its kind, Genesis Eco Drain[®] eliminates the need for traditional installation materials and allows for a full warranted surface!

Advanced Drainage Solutions

The Genesis Eco Drain[®] System is a patented, recyclable HDPE drainage system for use under artificial grass and pavers as an alternative to traditional rock base. It can be installed on almost any surface, and provide a solid and comfortable foundation along with superior drainage for any artificial turf product.

Ditch the Base Rock

Using the Genesis Eco Drain[®] System significantly reduces or completely eliminates many of the challenges of installing thousands of pounds of drain rock. Designed for all kinds of installation techniques, Genesis Eco Drain[®] is the perfect rock base alternative.



ARTIFICIAL TURF INSTALLATION COST*

*Based on 1500 sq ft Install.
Prices noted below are industry averages
across all 50 states.

	WITH GENESIS ECO DRAIN	WITHOUT GENESIS ECO DRAIN
Remove 6" Dirt	\$0	\$1,200
Soil Testing and Disposal for Dirt	\$0	\$1,800
4" 57 Stone	\$0	\$800
1" Stone Fines	\$0	\$450
2 Days Pay for Installation Crew	\$0	\$2,800
Equipment Rental for Stone Base Work	\$0	\$850
Ground Preparation	\$800	\$800
Composite Nailer Board	\$200	\$200
Genesis Eco Drain	\$3,000	\$0
Average 75oz US Artificial Turf	\$3,750	\$3,750
Average Infill Cost	\$1,200	\$1,200
1 Day Pay for Installation Crew	\$1,500	\$1,500
INSTALLATION TIME	1-1.5 Days	3-4 Days
TOTAL COST	\$10,450	\$15,350

COST SAVINGS **\$4,900**

PAVER INSTALLATION COST*

*Based on 1500 sq ft Install.
Prices noted below are industry averages
across all 50 states.

	WITH GENESIS ECO DRAIN	WITHOUT GENESIS ECO DRAIN
Remove 6" Dirt	\$0	\$1,500
Soil Testing and Disposal for Dirt	\$0	\$2,200
4" 57 Stone	\$0	\$1,600
1" Stone Fines	\$0	\$450
2 Days Pay for Installation Crew	\$0	\$2,800
Equipment Rental for Stone Base Work	\$0	\$850
Ground Preparation	\$800	\$800
Paver Product	\$6,000	\$6,000
Leveling Sand	\$2,200	\$2,200
Genesis Eco Drain	\$3,000	\$0
1 Day Pay for Installation Crew	\$1,500	\$1,500
INSTALLATION TIME	1-1.5 Days	3-4 Days
TOTAL COST	\$13,500	\$19,900

COST SAVINGS **\$6,400**